Notes:

Do not scale from this drawing.
Use figured dimensions only.
All errors and omissions to be reported to the Architect.
This drawing to be read in conjunction with relevant consultant's drawings.
All dimensions are in millimetres and all levels are in meters to match Datum unless otherwise noted.
All levels given are relative to Ordnance Datum.

Contractor Design responsibility
It is noted that there are many elements within the works that require contractor design, and will be subject to certification as part of BCAR - see Preliminary Inspection Plan for clarity on certification required.

© This drawing or design may not be reproduced without permission.

GENERAL NOTES

EXTENT OF PLANNING APPLICATION OUTLINED IN RED

THIS DRAWING TO BE READ IN CONJUNCTION WITH-
ARCHITECT'S DRAWINGS
CONSULTANT ENGINEER'S DRAWINGS AND SPECIFICATIONS
LANDSCAPE ARCHITECT'S DRAWINGS AND SPECIFICATIONS

Reproduced under Licence No. CYAL50250518
Copyright Ordnance Survey Ireland/ Suirbhéireacht Ordanáis Éireann

KEY TO FINISHES

- PC CONCRETE PAVING WITH NATURAL STONE AGGREGATE TOP SURFACE - 'Silver Granite' colour
- PC CONCRETE PAVING WITH NATURAL STONE AGGREGATE TOP SURFACE - 'Graphite' colour
- HOME ZONE/ SHARED SURFACE AREA
  Parking spaces - Permeable 'Bracken' coloured PC Block paving, 'Black top' macadam carriageway with raised 'Buff' coloured macadam shared surface and 150mm wide flush PC concrete kerbing and drainage channels to delineate
- COMPACTED GRAVEL
  'Ballyluk', 'Buff' coloured
- INDICATIVE PLAY AREA
  Hardwood Play Grade Chip
  Tested to BSEN 1177:1998 Safety Standard
- IN-SITE CONCRETE FOOTPATH
  Brushed finished
- CRECHE PLAY SPACE
  Wetpour colourd play safety surfacing
- MOWN GRASS /SEEDING
  on min. 150mm topsoil - Dashed line represents gentle grass mounding
- GENERAL SHRUB AND GROUNDCOVER PLANTING MIX
  on minimum 450mm topsoil
  Refer to landscape consultant's planting schedule for details
- SWALE/ WETLAND PLANTING MIX
  Refer to landscape consultant's planting schedule for details
- HEDGE PLANTING ON MINIMUM 600mm TOPSOIL
  Refer to planting schedule and typical planting detail
  Dashed red line indicates timber post and wire fencing within hedge planting
- BENCH AND SCULPTURAL SEATING
- TREE PLANTING
  IN MINIMUM 1.2m3 TOPSOIL
  Refer to planting schedule and typical planting details
- FEATURE TREE PLANTING
  IN MINIMUM 1.2m3 TOPSOIL
  Min. 25 - 30 cmg
  Refer to planting schedule and typical planting details
- EXISTING TREE/HEDGEROW TO BE PROTECTED AND RETAINED Refer to Arborist tree survey, associated report and M+A Tree Protection Drawing

Revisions:

Rev	Description	Date	By
P04	Issued for Planning	06/04/22	PMc
P03	Final issue incorporating all commentary	15/10/21	PMc
P02	Amendments added	29/09/21	PMc
P01	Amendments added-DT draft issue	17/09/21	PMc

Project:
Devoy Barracks, Naas, Co. Kildare

Client:
Land Development Agency

Title:
Proposed Site Layout- Undercroft

Drawing / Document Name:
Project Number | Project | Originator | Volume | Level | Type | Role | Sheet Number
19024DEV-MCO-00-ZZ-DR-A- 0512

Suitability Status : Code - Description | Revision:
S4- For Stage Approval | P-04

Scale @ A1	Drawn:	Checked:	Date:
1:500	PMcN	PMcN	Sept 2020

COADY ARCHITECTS
Mt Pleasant Business Ctr, Ranelagh, Dublin 6, D06 X7P8
Unit 8A Oran Point, Main St, Oranmore, Co. Galway, H91 Y36X
01 497 6766 | 091 788 325 | admin@coady.ie | www.coady.ie

MCORM
McCROSSAN O'ROURKE MANNING ARCHITECTS