

Electric Vehicle Charging Strategy

Proposed Residential Development at Kilnahue & Gorey Hill, Carnew Road & Kilnahue Lane, Gorey, Co. Wexford

KERRIGAN CONSULTING

DOCUMENT REVISION HISTORY			Ref:	250018-KER-XXXX-XX-RP-E-000001
Rev	Author	Verified By	Date	Comments / Status
00	R. Kerrigan	A. Harris	07/07/2025	Draft for Comment
01	R. Kerrigan	A. Harris	31/10/2025	Draft for Planning
02	R. Kerrigan	A. Harris	04/12/2025	Issued for Planning

©2025 Kerrigan Consulting Engineering Limited

Kerrigan Consulting Engineering Limited shall not be liable in whole or part for any use of this document beyond such purpose(s) as the same was originally prepared or provided nor shall Kerrigan Consulting Engineering Limited be liable for any misinterpretation as to such intended purpose(s).

Contents

1-0 INTRODUCTION 3

2-0 EV CHARGING REQUIREMENTS 4

2-1 Building regulations (Domestic) 4
2-2 Building regulations (Non-Domestic) 4
2-3 Wexford Co. Co. feedback 4
2-4 Wexford County Development Plan 2022-2028 4
2-5 planning stage considerations 4

3-0 CURRENT EV CAR MARKET 5

3-1 Current EV Usage in Ireland 5
3-2 Popular EV Models & Battery Size 5
3-3 Charging Patterns & Frequency 5
3-4 Estimated Future EV Car Usage 6

4-0 EV CHARGING OPTIONS 6

4-1 7.0kW Charger 6
4-2 Fast 22.0 kW Charger 6
4-3 Electric Vehicle Charging Infrastructure Report 2022-2025 7
4-4 Estimated Future EV Car Usage 7

5-0 EMBODIED CARBON ASSOCIATED WITH FUTURE EV CHARGING PROVISION 7

6-0 FUTURE EV CHARGER INSTALLATION COSTS 8

7-0 PROPOSED EV CHARGING INFRASTRUCTURE 9

7-1 Dwellings with On-Curtilage Parking 9
7-2 Off-Curtilage Parking 9
7-3 Creche Parking 10

8-0 CONCLUSION 11

1-0 INTRODUCTION

Kerrigan Consulting has been appointed by Glenveagh Homes to review the provision of electric vehicle charging stations and infrastructure to off-curtilage surface parking spaces on new residential development in Gorey, Co. Wexford.

This report will review the requirements under Building Regulations (Technical Guidance Document Part L) and Wexford County Council.

The aim of this report is to provide guidance on achieving the minimum requirements under the Building Regulations, while also future proofing the residential developments to meet the likely increased uptake of electric vehicles in the future.

The proposed Large Scale Residential Development (LRD) includes the construction of 413 no. residential units, a creche, and all associated site development works. A full description is provided in Chapter 2 of the EIAR and in the statutory notices. The majority of dwellings will have on curtilage parking, but 92no. dwellings will have on-street/ off curtilage parking only. The creche will have its own dedicated parking area with 11no. parking spaces and a drop off area. There are 141 no. off-curtilage/ communal parking spaces associated with the dwellings and 26no. visitor parking spaces.

2-0 EV CHARGING REQUIREMENTS

2-1 BUILDING REGULATIONS (DOMESTIC)

Under current Building Regulations (Technical Guidance Document Part L), there is a requirement for:

- Ducting or cabling for a future electric vehicle charger (EVCH) to be installed in all individual dwellings with on curtilage parking.
- Ducting or cabling for EVCHs to be installed to each parking space on multi-unit buildings (apartments, duplexes, etc.) where parking is provided inside or within the curtilage of the building.

There are no requirements in TGD Part L relating to dwellings with off-curtilage parking.

There is also no specific guidance on the recommended capacity of future EVCHs, diversity of their usage or ducting layouts (e.g. duct sizes, how many EVCHs can be provided on a single system, etc.).

2-2 BUILDING REGULATIONS (NON-DOMESTIC)

Under current Building Regulations (TGD Part L, Conservation of Fuel and Energy – Buildings other than Dwellings), there is a requirement for:

- Buildings with at least 10 car parking spaces should have at least 1 EV charger installed.
- Ducting or cabling for a future electric vehicle charger (EVCH) to be installed in 20% of all parking spaces inside or adjacent to the building.

Similarly to the guidance for dwellings, there is no specific guidance on the recommended capacity of future EVCHs, diversity of their usage or ducting layouts (e.g. duct sizes, how many EVCHs can be provided on a single system, etc.).

2-3 WEXFORD CO. CO. FEEDBACK

The feedback issued by Wexford County Council on the preliminary planning documentation commented that: *Electric vehicle regarding (sic) points must be provided in all driveways. Charging points must be provided for 20% of all other spaces. It is recommended that charging points should be located in spaces not assigned to specific dwellings to enable turnaround in charging the vehicles".*

2-4 WEXFORD COUNTY DEVELOPMENT PLAN 2022-2028

The Wexford Co. Co. Development Plan 2022-2028 makes a number of statements regarding EV charging within the Climate Action, Transportation Strategy and Infrastructure Strategy sections, however there is no specific guidance on the number or size of EV chargers that should be provided on new residential developments.

2-5 PLANNING STAGE CONSIDERATIONS

Electric vehicle charging needs to be considered early in the design process, as the provision of EV chargers and associated mini pillars, ducting, etc. will impact the site layout.

Important things to consider include:

On curtilage parking:

The majority of houses on the development have on curtilage parking and these houses will be pre-wired to enable 7.0kW EV chargers to be installed easily in the future.

Spatial requirements for Chargers & Ducting:

Locations for ESB mini-pillars and micro pillars, public lighting, substations, etc. need to be considered. These must all be located at least 2 metres apart from each other, so adequate space must be provided to install these, without impinging footpath widths.

Footpaths and off curtilage parking spaces should be designed with future EV charging in mind. EV chargers must not reduce access routes along footpaths (typically 2.0m wide footpaths are required). It is strongly recommended that a 500mm wide buffer zone is provided between footpaths and parking spaces, solely for the provision of EV chargers and ducting. This area should not be concreted/ tarmacked over, to make it easier to access the ducting below in the future.

Ownership/ Management of off curtilage parking:

All off curtilage parking spaces with EV charging infrastructure on the development will most likely have to be managed by the Owners' Management Company (OMC). Therefore, it will be the OMC's responsibility to maintain and run the installed EV chargers on the development and add any additional chargers in the future.

All ductwork, mini pillars, chargers, etc. associated with proposed and future EV chargers must be installed on OMC property and is not allowed to cross public footpaths, road, etc. This will necessitate a 500mm wide buffer zone is added between parking spaces and public footpaths to accommodate all ducting, chargers, etc. This zone will be incorporated into the OMC's management.

EV Charger Locations

The locations of EV charging points being installed initially should also be considered and ideally these should be banked together, within walking distance (3-5 minutes) of any dwellings with off curtilage parking.

EV chargers should be installed in communal/ visitor parking spaces and not ones specific to individual dwellings.

This strategy of provide charging hubs for users with multiple chargers will also reduce the installation costs and provide a more user-friendly installation for the residents.

3-0 CURRENT EV CAR MARKET

3-1 CURRENT EV USAGE IN IRELAND

Fully electric EVs currently represent 5% of the 2.3 million private cars[1] (approximately 110,000) in Ireland.

The government have stated repeatedly that the adoption of EVs will play a significant role in reducing CO_2 emissions and achieving its various greenhouse gas emission targets. With this in mind, they aim to electrify one-third of the private car fleet by 2030[2]. This would mean approximately 850,000 EVs will be on the Irish roads in 2030.

If these targets are achieved, the number of fully electric EVs in Ireland will increase by 770% in the next 6 years and the charging infrastructure needs to be in place to meet this future demand.

As things stand, there was a well-publicised downturn in EV sales in 2024 and these targets are highly unlikely to be achieved. It is more likely that there will be a maximum of 400,000 EVs in Ireland in 2030 (still a significant increase).

3-2 POPULAR EV MODELS & BATTERY SIZE

Based on new vehicle registrations between January 2024 and April 2024, the following are the most popular EVs in Ireland[3]:

- VW ID 4 (77kW battery)
- Hyundai Kona (65.4kW battery)
- Tesla Model 3 (82kW battery)
- Skoda Enyaq (77kW battery)
- MG MG4 (64kW battery)

The efficiency of cars above varies slightly and are worse in winter time, when the external temperatures are lower. For the purposes of this report, we have used an efficiency of 0.21kW/km based on the average real world range in cold weather conditions (mix of city and motorway driving) of the 5 car models above[4].

Car manufacturers recommend that the battery levels are maintained at between 20% and 80% most of the time to prolong the battery life. They also suggest that fast chargers (e.g. 50/ 125kW) are not used all time for the same reason.

Therefore, the average real-world range of the vehicles are[5]:

- VW ID 4 – 375km range (range 300km, when battery charged to 80%)
- Hyundai Kona – 325km range (range 260km, when battery charged to 80%)
- Tesla Model 3 – 345km range (range 276km, when battery charged to 80%)
- Skoda Enyaq – 380km range (range 304km, when battery charged to 80%)
- MG MG4 – 305km range (range 244km, when battery charged to 80%)

3-3 CHARGING PATTERNS & FREQUENCY

The average private car in Ireland travels 16,352km per year[6] (44.8km/day), while the average distance that commuters travel to work is 16.8km[7].

There is no clear data available for average EV usage, therefore for the purposes of this report we have assumed that the average EV driver travels the same distance as the average driver in Ireland.

Based on the national average, the car with the smaller battery above (MG MG4) would need to be charged every 3 or 4 days, while always maintaining their battery between 20% and 80%, in accordance with the manufacturer's guidelines.

[1] Will 41,000 electric cars be sold in Ireland in 2024? (rte.ie)
[2] Will 41,000 electric cars be sold in Ireland in 2024? (rte.ie)
[3] Electric Cars in Ireland - Some Facts and Figures - Money Guide Ireland
[4] Most efficient electric cars - EV Database (ev-database.org)
[5] Most efficient electric cars - EV Database (ev-database.org)
[6] Transport Omnibus 2019 - Central Statistics Office (no data available for 2022 or 2023. 2020 and 2021 data not used due to various Covid-19 restrictions that were in place at the time).
[7] Commuting to Work - CSO - Central Statistics Office

Based on the above information and data published by the government[8], the average session will consume between 30 and 40kW of electricity.

3-4 ESTIMATED FUTURE EV CAR USAGE

As referenced above, EV car ownership is likely to increase considerably in the next six years (between 360% and 770% increase), therefore current data on public EV charging stations needs to take this into consideration when making provision for EV chargers in the future.

As stated above, a typical EV car driver will need to charge their car every 3 or 4 days, with an average charging session requiring between 30 and 40kW of electricity, which is unlikely to change in the future.

4-0 EV CHARGING OPTIONS

There are a range of EVCH available on the Irish market, ranging from slow 3.0kW chargers to super-fast 150kW versions.

The cost of the chargers and the associated infrastructure vary hugely, and the type of charger installed should suit the local requirements (e.g. slower chargers for homes, offices, etc.), where the cars are likely to be parked up for a number of hours/ overnight, with faster chargers (e.g. 50kW and 150kW) in motorway service stations, town centre public car parks, etc.

The future running costs and maintenance of the chargers should also be considered. On this development the management and maintenance of the EV infrastructure will most likely be the responsibility of the OMC.

EV chargers are typically managed by a specialist company, who will be responsible for handling payments and undertaking annual maintenance, repairs, etc. For this service they will charge a handling fee of between 7% and 10% on all transactions and approximately €600 for the annual service. The servicing and any costs relating to repairs, replacements of parts, etc. will be recouped through higher tariffs, therefore the more often a charger is used, the cheaper the tariffs should be.

A number of EV specialists will provide a two-tier payment structure, where residents of a development can avail of cheaper tariffs that non-residents. This will be discussed with and agreed with the EV specialist, prior to going into contract with them.

In the future, when the need arises for additional EV chargers, the OMC will need to engage the services of a specialist to install and manage the new EV chargers. Again, the cost of this work will need to be recouped through higher charging tariffs. Good design, taking into account future EV charging requirements should reduce the civils costs associated with these works and lead to lower tariffs in the future.

Taking into consideration the average battery size of the 5 most popular EV models above (73kW), the average car usage and recharging patterns in Ireland (Sections 3-2 and 3-3) and information from an EV charging specialist (EasyGo), the average charging session will consume between 30 and 40kW. We have used 35kW for the basis of the calculations below.

4-1 7.0KW CHARGER

Based on the average car usage (44.8km/ day), the average car will need to be charged every 3 or 4 days. A 7kW charger will provide an average 35kW charge in 5 hours. Current government guidelines[9] and the ESB[10] advise that a typical 7kW charger will take longer (at least 7 hours) to charge a car on average. As most car charging takes place in the evening time during the week, it is unlikely that more than 1 car will use an EVCH of this type for a full charge on a typical weekday (a person plugging their car in a 5pm is unlikely to move their car after 10pm). At weekends, the charger is more likely to be used a second time in the morning/ afternoon.

Therefore, a 7kW charger is likely to be used a maximum 9 times a week and suitable for 3 or 4 regular users.

4-2 FAST 22.0 KW CHARGER

Using the same assumptions above a 22kW charger will provide an 35kW charge in 1 hour 36 minutes. This is broadly in line with the ESB, who advise that a typical charger with will take up to 2 hours to charge a car on average[11].

It should be noted however that a number of EV models currently on the market do not accept a 22kW charge and therefore limit the charge to 11kW[12]. This may change in the future, but for the purposes of this report we will work on a basis that all cars will only charge at 11kW, and so the average charge times are likely to be between 2 and 4 hours as per government[13] and ESB[14] advice.

[8] Department of Transport – Electric Vehicle Charging Infrastructure Strategy 2022-2025
[9] Department of Transport – Electric Vehicle Charging Infrastructure Strategy 2022-2025 – Table B1
[10] ESB Networks Overview of Public On-Street Electric Vehicle (EV) Charging ≤49kVA(71A) – Table 1
[11] ESB Networks Overview of Public On-Street Electric Vehicle (EV) Charging ≤49kVA(71A) – Table 1
[12] Department of Transport – Electric Vehicle Charging Infrastructure Strategy 2022-2025.
[13] Department of Transport – Electric Vehicle Charging Infrastructure Strategy 2022-2025 – Table B1
[14] ESB Networks Overview of Public On-Street Electric Vehicle (EV) Charging ≤49kVA(71A) – Table 1

Given the faster charging times, a much higher turnover of cars using is chargers will be possible. Software can be installed on the charger to limit the time a car can be plugged in, with financial penalties to ensure a single user does not monopolise a charger after a set period of time (say 4 hours).

Based on the assumptions above relating to the most common charging times, it is likely that 1 or 2 cars could utilise a single charger every evening. Morning or daytime charging will also be more likely, given the reduced charging times. Taking this into account a single charger could easily be used 2 or 3 times a day during the week and 3 or 4 times a day at weekends.

Therefore, a 22kW charger could be used up to 23 times a week and suitable for up to 11 regular users.

By installing 22kW chargers only on a development, the number of chargers required to meet demand will be greatly reduced, which will also reduce the civil engineering works required (e.g. ducting requirements across the site). This would be a more cost-effective solution to meet all the future needs of the development, reduce running costs for the OMC and lead to reduced charging tariffs for the end user.

4-3 ELECTRIC VEHICLE CHARGING INFRASTRUCTURE REPORT 2022-2025

This report sets out the government's targets for the provision of publicly accessible EV charging locations around the country. As part of the report, it references residential/ neighbourhood charge points, recommending that chargers with an output of up to 22kW are installed in these locations.

4-4 ESTIMATED FUTURE EV CAR USAGE

As stated in Section 3-4 above, the EV charging infrastructure needs to be capable of meeting the future EV charging demand in both the short/ medium term (up to 2030) and longer term (100% EV ownership).

5-0 EMBODIED CARBON ASSOCIATED WITH FUTURE EV CHARGING PROVISION

As can be seen from the calculations in Section 4-1, a 7kW charger will provide adequate charging capacity for 3 or 4 users. By installing 22kW chargers as a standard, the number of chargers required to meet 100% EV usage is further reduced (i.e. as few as 9% of parking spaces, with 22kW charger fitted could provide sufficient capacity for 100% of parking spaces).

With this in mind it is worth considering the waste of materials, work and embodied carbon associated with the installation materials in the ground that will never be required.

The planning advice from Wexford Co. Co. stated that EV chargers should be installed in 20% of the off-curtilage and visitor parking spaces provided, therefore installing 29no. 7kW EV chargers would comply with this requirement. As per the previous calculations, these chargers could meet the charging requirement of around 87 cars.

Alternatively, 6no. 22kW chargers would provide adequate charging capacity for up to 66 users. Ducting for an additional 6no. parking spaces would easily meet the demands of 100% EV ownership at some point in the future, catering for up to 132 EV owners.

Following this strategy would considerably reduce the amount of ducting required in the ground, reducing construction costs and embodied carbon.

To cater for each EV charging hub, a concrete mini pillar chamber and ducting is typically installed at construction stage, which will cater for up to 6 parking spaces, depending on the parking layout. By installing 22kW chargers only, 3no. EV charging system/ hub could meet the requirements of the whole development, with capacity for up to 132 users and negate the requirement to install up to 6 other systems that would be required to provide 7kW chargers in 20% of spaces.

The BSRIA Guide, Embodied Carbon – The Inventory of Carbon and Energy (ICE) provides advice on how to calculate the embodied carbon of various building materials (e.g. precast cement, 0.168kgCO_2/kg and uPVC ducting, 2.56kgCo_2/kg) and how to consider other factors (e.g. wastage and transport).

Typically an EV charging system will consist of an ESB mini pillar, concrete chamber, 125mm ducting to each proposed EV charger, EV chargers and 125mm ducting to the nearest ESB mini pillar. Where provision is being made for future charging only, only the concrete chamber and 125mm ducting will be installed initially.

Based on the BSRAI data, a typical concrete chamber weighing 880kg and will have approximately 152kg of embodied carbon, assuming they are manufactured in Ireland. A typical EV installation will consist of approximately 50 metres of 125mm underground ducting. Allowing for 10% wastage, this will have approximately 156kg of embodied carbon. Therefore, over 300kg of embodied carbon is required to provide underground services to a future EV charging hub. Across this development, materials with over 1,800kg of embodied carbon would be installed unnecessarily. This excludes other elements of the installation which are harder to calculate (e.g. carbon emissions associated with digging and back filling the trenches, omission of the 500mm buffer zone between the parking spaces and footpaths, etc.) which significantly increase the carbon emissions connected with the installation.

6-0 FUTURE EV CHARGER INSTALLATION COSTS

The costs associated with the future installation of EV chargers is an important consideration and one that is not covered in detail in the current regulations and guidelines.

Where on curtilage parking is provided to a house, the installation of a new EV charger will be straightforward and can be carried out by a competent electrician, utilising preinstalled cabling, a standard home charger and without an upgrade to the dwellings ESB supply in most cases.

It is not as simple in the case of off curtilage parking spaces. As the off-curtilage parking spaces will not be owned by specific homeowners and will instead be managed by the OMC. To install an EV charger in one of these spaces, the OMC will need to approve the installation and be responsible for the upfront costs associated with the installation or allow an independent EV provider to install and run the EV chargers as a private enterprise.

The most common EV charger installation scenarios will be:

a) 7.0kW EV charger added to existing EV charger hub, with all ducting and ESB supply in place.
b) 22.0kW EV charger added to existing EV charger hub, with all ducting and ESB supply in place.
c) 7.0kW EV charger with existing ducting in place but no ESB connected.
d) 22.0kW EV charger with existing ducting in place but no ESB connected.
e) Upgrade existing 7.0kW charger to 22.0kW type.

We will now review the installations costs for each of these situations. For the purposes of this cost comparison, we will assume that all ducting and underground chambers are installed correctly, and no major civils works are required.

7.0kW EV charger added to existing EV charger hub, with all ducting and ESB supply in place.

New ESB 49kV/ 3phase supply	N/A
New ESB mini pillar supply & installation	N/A
New dual 7.0kW EV charger installation & commissioning	€5,000.00
Total Budget Cost (excluding VAT)	€5,000.00

22.0kW EV charger added to existing EV charger hub, with all ducting and ESB supply in place.

New ESB 49kV/ 3phase supply	N/A
New ESB mini pillar supply & installation	N/A
New dual 22.0kW EV charger installation & commissioning	€7,000.00
Total Budget Cost (excluding VAT)	€7,000.00

7.0kW EV charger with existing ducting in place but no ESB connected.

New ESB 49kV/ 3phase supply	€5,000.00
New ESB mini pillar supply & installation	€2,000.00
New dual 7.0kW EV charger installation & commissioning	€5,000.00
Total Budget Cost (excluding VAT)	€12,000.00

22.0kW EV charger with existing ducting in place but no ESB connected.

New ESB 49kV/ 3phase supply	€5,000.00
New ESB mini pillar supply & installation	€2,000.00
New dual 22.0kW EV charger installation & commissioning	€7,000.00
Total Budget Cost (excluding VAT)	€14,000.00

Upgrade existing 7.0kW charger to 22.0kW type.

New ESB 49kV/ 3phase supply	N/A
New ESB mini pillar supply & installation	N/A

New dual 22kW EV charger installation & commissioning	€7,000.00
Total Budget Cost (excluding VAT)	€7,000.00

As can be seen from the budget figures above, there is a significant cost increase associated with installing the first EV charger to a system, compared to adding one to an existing system. These additional costs will need to be paid upfront by the OMC and recouped from the people using the chargers through higher charging tariffs.

Higher charging tariffs will lead to less people using the chargers and discourage people on these developments from switching to EV vehicles.

We propose installing active 22.0kW chargers in both charging hubs, so that the ESB supplies and mini pillars will be in place initially, thereby reducing the cost of adding additional EV chargers in the future.

Standard Approach to Compliance with Wexford Co. Co. EV Charging Requirements

If we consider the typical approach to a development of this nature with 141no. off-curtilage/ communal/ visitor parking spaces and a planning requirement for EV chargers to be installed in 20% of parking spaces. The following installation would achieve planning compliance:

- 141 parking spaces.
- 28no. 7.0kW chargers installed initially (8no. systems, with between 2 and 6no. chargers).

Based on the calculations in Section 4-0, the above installation would be suitable to meet the charging demand of up to 84 average EV users. It should be noted that the parking spaces are a mix of allocated off-curtilage/ communal/ visitor parking (50 assigned spaces serving 28 houses, 65 communal spaces serving apartments/ duplexes and 26 visitor spaces). This is in excess of the requirements to meet even the best-case government targets for EV ownership in 2030, meaning that most of the chargers will either not be used at all, or massively underused for the foreseeable future. This could also lead to other problems (e.g. vandalism). Slower 7.0kW chargers are unlikely to be used by people outside of the developments, due to low recharging times. There is also a risk that by the time the installed chargers are actually required to meet higher levels of EV ownership, they are 5 to 10 years old and are nearing the end of their expected working life.

Proposed Alternative Solution:

The following installation would meet the actual EV charging requirements of the development:

- 141 parking spaces, served by 3no. EV charging hubs (6no. spaces).
- 6no. 22kW chargers installed initially.
- Ducting provided to 6 other parking spaces.

Based on the calculations in Section 4-0, the above installation would be suitable to meet the charging demand of up to 66 average EV users. This installation would exceed the requirements for even the best-case government targets for EV ownership in 2030 and provide the residents will a better facility providing faster charging. Faster 22kW chargers are far more likely to be used by people outside of the developments, due to faster recharging times. 3no. charging hubs with 12no. 22kW chargers in total would also easily meet the requirements for 100% EV ownership at some point in the future.

The information above furthers the argument that a smaller number of suitably positioned EV charging hubs with high output (e.g. 22.0kW) EV chargers is a better solution to providing chargers in all off-curtilage parking spaces. It will lead to a better facility for the residents, with faster charging times, lower running costs and be easier to maintain by the OMC/ EV specialist.

7-0 PROPOSED EV CHARGING INFRASTRUCTURE

7-1 DWELLINGS WITH ON-CURTILAGE PARKING

321 of the dwellings will have on curtilage parking and will be pre-wired to enable home EV chargers to be installed in the future, in accordance with TGD Part L and the Wexford Co. Co. County Development Plan.

7-2 OFF-CURTILAGE PARKING

The remaining 92 dwellings will not have on curtilage parking.

As stated earlier, there is no specific requirement in TGD Part L relating to public parking spaces.

Parking spaces will be designated to individual houses but not to individual apartments/ duplexes, but most parking spaces will become associated with a particular apartment/ duplex (e.g. parking spaces nearest an apartment/ duplex will predominately be used by the occupants of that apartment/ duplex most of the time). By installing EV chargers in these communal parking spaces there is a risk that the occupants of the houses will use the space as their own, regardless of whether they have an EV or not.

7-3 CRECHE PARKING

Under current Building Regulations (TGD Part L, Conservation of Fuel and Energy – Buildings other than Dwellings), there is a requirement for:

- Buildings with at least 10 car parking spaces should have at least 1 EV charger installed.
- Ducting or cabling for a future electric vehicle charger (EVCH) to be installed in 20% of all parking spaces inside or adjacent to the building.

As there are 11 parking spaces provided for the creche, 1no. EV charger will be required, with ducting for a second future charger.

8-0 CONCLUSION

The current Wexford Co. Co. Development plan and planning guidance require active EV chargers to be installed in 20% of all off-curtilage parking spaces. As detailed in the report, these requirements are not appropriate and do not take into consideration capacity of different EV chargers on the market, installation and running costs, or how the chargers will be maintained in the future.

Based on the data in this report, an average EV driver needs to charge their car 2 or 3 times a week, meaning that a 7.0kW public charger could cater for 3 or 4 EV drivers, while a 22kW charger could cater for up 11 EV drivers.

We propose to move away from the standard requirement of providing chargers to 20% of parking spaces and instead provide a bespoke EV charging solution for the development.

EV chargers should be grouped together in 3no. charging hubs, within walking distance of all dwellings with no on curtilage parking. These hubs should have ducting installed for additional chargers to be installed in the future. The locations of the proposed EV charging hubs are indicated on Deady Gahan's Proposed Parking, Bin and Bike Plan Strategy drawing 24058/P/011. The savings made by not installing unnecessary ductwork and chargers will be used to upgrade the standard 7.0kW charger to a 22.0kW version.

This approach should make servicing easier and cheaper, as the chargers, mini pillars, etc. will be grouped together and also make the developments more appealing to private EV operators in the future to operate and expand the initial EV offering.

Additionally, a discount rate will be agreed with the EV specialist for residents of the developments as part of the long term operational and maintenance contract.

Contact

Ronan Kerrigan
087 387 9267
rkerrigan@kerriganconsulting.ie

©2025 Kerrigan Consulting Engineering Limited
Kerrigan Consulting Engineering Limited shall not be liable in whole or part for any use of this document beyond such purpose(s) as the same was originally prepared or provided nor shall Kerrigan Consulting Engineering Limited be liable for any misinterpretation as to such intended purpose(s).

KERRIGAN
CONSULTING